



**GENERAL NOTES AND INSTALLATION BY CONTRACTOR:**

1. FILL SAMPLE PIPING w/ HEAVILY CHLORINATED WATER WHILE MAINS ARE BEING STERILIZED.
  - 1.1. MIX 2 TABLESPOONS OF H.T.H. PER GALLON WATER IN SAMPLE PIPING. CONTACT TIME TO BE 30 MINUTES MINIMUM.
2. WATER MUST BE RUNNING FROM BALL VALVE (SLOWLY) FOR 30 MINUTES MINIMUM BEFORE SAMPLING.



GreenvilleWater

**2-INCH BLOWOFF PIPING  
(FOR SAMPLING)**

REVISION DATE:

9.11.2024

(NOT TO SCALE)

DETAIL NO:

12.1