



**GENERAL NOTES AND INSTALLATION BY CONTRACTOR:**

1. AIR RELEASE VALVES REQUIRED AS DIRECTED ON ALL WATER MAINS 10" AND LARGER.
2. ALL EXCAVATING TO BE DONE BY CONTRACTOR.
3. APPROXIMATE SIZE WHERE TAP IS MADE IS 3' x 5' (6" BEHIND AND UNDER MAIN WITH REMAINDER OF EXCAVATION ON TAP SIDE OF MAIN).
4. EXCAVATION FOR AIR RELEASE BOX TO BE 3' x 3' x 21" DEEP
5. SERVICE LINE SHALL HAVE 36" MINIMUM COVER UNDER ROADSIDE DITCH.
6. BOX SHALL NOT BE PLACED IN DRIVEWAY
7. CONTRACTOR TO CONTACT G.W. ENGINEERING TO REPORT WHEN READY FOR TAP TO BE MADE AND AIR RELEASE VALVE TO BE SET.



GreenvilleWater

**AIR RELEASE VALVE**

REVISION DATE:

9.11.2024

(NOT TO SCALE)

DETAIL NO:

15